BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No.

Name of Work: Maintainance of Drilled BBMP Borewells in ward no 10, (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Quantity	Description	Unit	Rates In Figures	Rates In Words
1	28	Lifting of Submersible pump set as per Soecification and direction etc., complete and as per the directions of the Engineer-in-charge of the work	Each	850.00	
2	28	Transportation of pumping machineries etc., complete and as per the directions of the Engineer-in-charge of the work	Each	900.00	
3	28	Labour charges (over hauling) etc., complete and as per the directions of the Engineer-in-charge of the work	Job	550.00	
4	28	A) Repairs to Motor: Rewinding of submersible pump sets with copper insulation wire of suitable gauge as per ISI specification with guarantee of 6 months. (Above 10 HP upto 20 HP add Rs.150/- for every ½ HP) etc., complete and as per the directions of the Engineer-in-charge of the work		4750.00	
5	28	Starter (with one year Guarantee) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	5050.00	
6	28	Rotor (with one year Guarantee) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	4700.00	
7	28	Upper Flange etc., complete and as per the directions of the Engineer-in-charge of the work	No.	350.00	
8	28	Lower Housing etc., complete and as per the directions of the Engineer-in-charge of the work	No.	650.00	
9	28	Carbon Housing etc., complete and as per the directions of the Engineer-in-charge of the work	No.	475.00	
10	28	Thrust bearing block assembly complete with Segment bearing pad etc., complete and as per the directions of the Engineer-in-charge of the work	No.	1150.00	
11	28	Oil Seal etc., complete and as per the directions of the Engineer-in-charge of the work	No.	125.00	
12	28	Oil Seal Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	150.00	
13	420	Guide vane etc., complete and as per the directions of the Engineer-in-charge of the work	No.	175.00	
14	420	Impeller Shell moulded with aluminium Bronze) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	425.00	

Sl. No.	Approved Quantity	Description	Unit	Rates In Figures	Rates In Words
15	28	Discharge outlet (D.O) Bearing D.O Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	445.00	
16	28	Steel Bush etc., complete and as per the directions of the Engineer-in-charge of the work	No.	150.00	
17	28	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) etc., complete and as per the directions of the Engineer-in-charge of the work	No.	950.00	
18	28	Non – return valve (NRV) assembly complete with rubber 'O' Ring etc., complete and as per the directions of the Engineer-in-charge of the work	No.	1350.00	
19	28	Cable Guard etc., complete and as per the directions of the Engineer-in-charge of the work	No.	150.00	
20	28	Brass Filter etc., complete and as per the directions of the Engineer-in-charge of the work	No.	250.00	
21	15	Re-erection charges of pumping machineries including overhauling and pointing etc., complete and as per the directions of the Engineer-in-charge of the work	Each	950.00	
22	50.00	Supplying of ISI marked galvanized mild steel tube (continously welded electric resistance welded (ERW) high frequency, induction welded (HFIW) Hot finished welded type of nominal bore given below screwed at both ends as per IS 554/1986 with latest amendments, pipes threaftes at one end and the other end protected asper specification in random lengths of 4 to 7 mtrs Confirming to IS 1239 part I/1990 with amendament 1-5 and with all its latest amendements if any. The pipes supplied should be with BIS mark etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	375.00	
23	15	Heavy Duty Collar 50 mm dia etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	130.00	
24	200.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	188.70	
25	30.00	Supplying of LTUG cable having aluminium condutor PVC insulated shethed, galvnised steel, wire / steel tap armoured cable with PVC outer sheathing 1.1 KV class.**P No. 68/ I No. 4(d) 4 core 16 Sqmm** etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	140.40	
26	30.00	Labour charges for laying of 1.1 K.V class UG cable (PWD Electrical SR-1999-2000, **P No. 69 / I No. Ia In existing trencg/duct 6Sqmm to 16 Sqmm)** etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	10.80	
27	20.00	Digging or trenching of 0.6m deep x 0.5 mtr wide refilling the trench to the required ground level and consolidating etc., complete (as per Civil SR KSRB **1-2 P-7)** etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	85.00	

Sl. No.	Approved Quantity	Description	Unit	Rates In Figures	Rates In Words
28	16.00	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class **etc., complete and as per the directions of the Engineer-in-charge of the work**	Mtr	345.00	
29	4.00	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., complete and as per the directions of the Engineer-in-charge of the work	No.	280.00	
30	36	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete and as per the directions of the Engineer-in-charge of the work	No.	180.00	
31	2	KSRB 13-7.1-4: Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	1579.40	
32	2	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spotetc., complete and as per the directions of the Engineer-in-charge of the work	No	227.90	
33	23400.00	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm @ Rs.0.33 etc., complete and as per the directions of the Engineer-in-charge of the work	Sq.Cm	0.33	

ಕರಡು ಟೆಂಡರ್ ಪಡಿಯಲ್ಲಿನ
ಶಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....( )
ಶಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿರುತ್ತಿದೆ

Superintending Engineer
Yelahanka Zone
BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92